

324

पूर्वोत्तर सीमा रेल

NORTH EAST FRONTIER RAILWAY

कार्यालय

मुख्य सतर्कता अधिकारी

मालीगाँव, गुवाहाटी-11

No. Z/VIG/68/05/A

Office of the

Chief Vigilance officer

Maligaon, Guwahati -11

दिनांक/Date: 07-10-2021

**Pr.CE, CAO/CON-I, II & III.  
DRMs/KIR, APDJ, RNY, LMG & TSK**

**Sub: System improvement regarding sending message to Vigilance Department for initial levels of blanketing work.**


Blanket layer of specified coarse, granular material of designed thickness is provided over full width of formation between sub grade and ballast. As per Unified Standard Specifications for Works & Materials, the measurement of blanket material should be done on the basis of finished cross sections. Thus, records of initial levels and final levels of blanketing are essential to work out the exact executed quantity of blanketing materials for the purpose of payment.

During investigation, irregularities in thickness /measurements/levels have been observed in the case of blanketing. Blanket material is a much costlier item than the earthwork. After execution, it is not possible to verify the authenticity of initial levels of blanket and therefore, there is every possibility of manipulation at later stage.

Therefore, in order to ensure proper measurement and to improve transparency following system improvement is suggested in connection with execution of blanket material-

“Message for recording initial levels of blanket material should be given to Vigilance Department. After sending the vigilance message, a waiting time of 07 days should be kept before start of blanketing work by the contractor.

In view of the above, all the concerned officials may be advised to adopt the above suggested system improvement. A copy of the instruction issued may be sent to this office for record.

  
07.10.21  
(बी. लकड़ा)

वरिष्ठ उपमहाप्रबंधक एवं  
मुख्य सतर्कता अधिकारी  
पू.सी.रेल/मालीगाँव